CENTEX HOMES

Appendix L

List of Contractor Do's & Don't's

DO:

- **DO** go to the Site Storm Water Compliance Representative with any questions regarding storm water pollution prevention or this list.
- **DO** place all trash and debris in the receptacles provided.
- **DO** use designated washout areas for cleaning equipment (e.g., concrete trucks must use the designated concrete washout area).
- DO report any spills of petroleum or other chemicals to the Site Storm Water Compliance Representative.
- **DO** immediately comply with any instructions given by the Site Storm Water Compliance Representative or other Centex personnel.

DON'T:

- DON'T allow any solvents, chemicals, or rinse liquids to drain into a street or storm drain, a creek, waterway, other water body.
- **DON'T** disable, damage, or interfere with any silt fence or similar erosion control.
 - For example, DON'T run over a silt fence or straw wattle or forget to replace any silt fence or straw wattle you temporarily relocate.
- DON'T disable, damage, or interfere with any inlet controls.
 - For example, DON'T remove inlet controls (unless an action is needed to prevent flooding) or place dirt or debris in or adjacent to inlet controls.
- DON'T disable, damage, or interfere with any storm water pollution prevention controls at construction entrances.
 - o For example, **DON'T** evade stone construction entrances.
- DON'T disable, damage, drive over, or interfere with any geotextile, matting, or mulch.
- DON'T disable, damage, or interfere with any other storm water pollution prevention controls.

Remember: The failure to comply with storm water requirements at this site is a breach of your contractual obligations and can result in economic sanctions or termination.